

Year 4 Combined Sewer Overflow Control Project Construction Meeting

July 9, 2025


Andrea Klopfenstein, P.E.
City Engineer



CITY OF
PEORIA



Purpose



Introduction to the project team



Recap of the project area and work to be completed



Construction schedule and sequencing



Questions





Project Team

District Council Member- Denise Jackson

djackson@peoriagov.org

Resident Engineer – Bryce Knowles 309-363-8665

gbknowles@mstutz.com

Construction Program Manager - Mandy Mooberry

309.494.8824 mmooberry@peoriagov.org

Contractor - Illinois Civil Contractors Inc. (ICCI)

Project Manager - Scott Reeise, P.E. 309.303.8660

sreeise@ilcivil.com





Project Team

Deputy Director/City Engineer– Andrea

Klopfenstein, P.E. 309.494.8816

aklopfenstein@peoriagov.org

Assistant City Engineer – Paola Mendez-

Silvagnoli, P.E. 309.494.8811


pmendez@peoriagov.org

CSO Program Manager – Kyla Dean, P.E.

414.755.1168 kdean@peoriagov.org

City of Peoria Public Works

309.494.8800 publicworks@peoriagov.org



Definitions



Combined Sewer



Combined Sewer
Overflow (CSO)




Green
Infrastructure (GI)



Consent Decree to Reduce CSO Discharges

- In December 2020, the City entered into a Consent Decree with U.S. EPA **to reduce CSO discharges** to the Illinois River
- **18-year implementation period**
 - Starting January 2022
 - Ending December 2039



How Project Locations Were Determined



Inlet locations – low point where water goes, GI needs to capture flow before it gets to inlet




Infiltration tests – used to determine the most suitable locations for GI



City's sewer model – used to determine the size of GI needed at each location

Location of Projects

- In the combined sewer area (black outline),
- Below the bluff (green shading), and
- In the existing right-of-way



Year 4 Project Area


- Green infrastructure to reduce stormwater flow to the sewer
- Will reduce CSO discharges to the Illinois River



Year 4
Preliminary
Project
Layout




Year 4 Project Layout




Year 4 Project Layout




Year 4 Types of Projects – Intersection Improvement




SECTION A-A



Year 4 Types of Projects – Mid Block Improvement



SECTION A-A



Construction Schedule and Sequencing



Schedule - Start: July 21, 2025*
Completion: end of 2026



Project Starting Locations:
Greenlawn & Antoinette
Westmoreland & Ann



Timing for each location varies
because the scope of work varies.



Construction Schedule and Sequencing



Multiple intersections will be closed. Follow marked detours.



Midblock improvements will close the road. Follow marked detours.



Pavement removal, storm sewer, curb and gutter will be done first with HMA pavement will be done later.

Utility Coordination

This project was coordinated with utility companies:

- | | |
|----------------------------|-------------------------------------|
| 1. Ameren Gas | 4. Greater Peoria Sanitary District |
| 2. Ameren Electric | 5. Telecommunication Companies |
| 3. Illinois American Water | |

Utility work may occur outside of the road project construction stage.



Coordination- ROW



Landscaping – remove and relocate anything you want to keep.



Irrigation Systems – contact your irrigation company to turn off and relocate the lines in conflict.



Invisible Dog Fence – remove and relocate the lines in conflict.



Sump pump and downspout drains – please talk to a team member to let us know where they are located.




If you need help to determine conflicts in your yard, please contact Bryce.

Items in the Right of Way (ROW)

Landscaping – remove and relocate anything you want to keep.

J.U.L.I.E flags- Utility markings and flags are used to identify underground utilities.



www.illinois1call.com



Common Issues

Landscaping- areas will be disturbed and look rough until the project is completed.

Pavement- areas will be temp surfaced until multiple locations are ready for the final surface.

Blowing grass clipping into the construction area or onto the finished pavement is not allowed.



Communication

Bryce is the main contact during construction:
gbknowles@mstutz.com 309-363-8665



The workers in the field know their task but might not know the big picture.





SW corner of Mary & Perry

Communication



Project Updates – Please note on sign in sheet if you would like to be included on **project update emails**.



Special Access– Please talk to a project team member.



Door hangers will be delivered to notify you of driveway, mail, or trash service impacts.



Questions

Learn More: PeoriaCSO.com

